Milijuli Kalinchowk Saving And Credit Co-operative Limited
Bhimeshwor-6, Charikot Dolakha

Price Quotation of
Mechanical

Date:-…………………..

SN.	Description of Item	Unit	Quantity	Rate (Rs.) without VAT	Rate in Words	Remarks
1	**AIR CONDITIONING WORK**					
a	**1.5 tonnes casette AC**					
	Capacity:-1.5 TR Gas Line:-5/8" Liquid Line:-3/8" Inverter Type Features: Auto restart, self diagnostic system, dehumidifier, auto-protection, air exchange device, intelligent defrosting, auxiliary electric heating system, hydrophilis film, smoke cleaning with multi folds evaporator. Make: Hitachi, Midea, Chigo or Equivalent	nos	1.00			
b	**1 tonne wall mount AC**					
	Capacity:-1 TR Gas Line:-1/2" Liquid Line:-1/4" Inverter Type Features: Auto restart, self diagnostic system, dehumidifier, auto-protection, air exchange device, intelligent defrosting, auxiliary electric heating system, hydrophilis film, smoke cleaning with multi folds evaporator Make: Hitachi, Midea, Chigo or Equivalent	nos	1.00			
c	**4 tonnes casette AC**					
	Capacity:-4 TR Gas Line:-7/8" Liquid Line:-1/2" Inverter Type Features: Auto restart, self diagnostic system, dehumidifier, auto-protection, air exchange device, intelligent defrosting, auxiliary electric heating system, hydrophilis film, smoke cleaning with multi folds evaporator Make: Hitachi, Midea, Chigo or Equivalent	nos	1.00			
d	**Copper Tubing 1 tonne and 1.5 tonnes**	r. ft.	1.00			
e	**Copper Tubing 4 tonnes**	r. ft.	1.00			
f	**Water Outlet**	r. ft.	1.00			
g	**Installation**	each	1.00			
2	**VENTILATION**					
a	**Fresh and Exhaust air Fans**					
	Capacity:-500 CFM Power Supply:-single Phase 220V, 50 Hz	nos	1.00			
c	**Ducting Work**					
	Supply,delivery,fabrication and installation of GI Sheet 24(G) for Dust works as per the issued drawing,complete with expansion bolts,threaded hanger,dust support Mild Steel channel hanger supports and silicon sealed as per specification and site conditions.	s. ft.	1.00			

Note :- All item mentioned above should be supply and install all complete as per the requirements of Office and instruction of Site Engineer.